

1060169

TO: STATE CORPORATION COMMISSION

8-16

API NUMBER 15-083-20,484.0000  
SE SE SE SEC. 21, T 21 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FOLKERTS TWIN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN

OPERATOR LICENSE # 5131

WELL TOTAL DEPTH 4553 147.97 FEET

OPERATOR: THUNDERBIRD DRILLING, INC PRODUCTION CSG: SIZE 4 1/2" @ 4539' WITH 150 SX

NAME AND PO BOX 97 SURFACE CASING: SIZE 8 5/8" @ 329' WITH SX

ADDRESS ELLINWOOD, KS 67526

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31528

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 2:15 PM DAY: 16 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MONTE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4304-07 SQUEEZED OFF WITH 150 SX CEMENT.

PUMP 30 SX CEMENT & 200# HULLS TO 4500'. GEL TO 1450'. CIRCULATE FROM 1450' TO 0'.

USE 50 SX CEMENT FOR BACKSIDE.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 16 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 50 SX CEMENT WITH 200# HULLS. PULLED TO 3970' AND MIXED 40 BBL GEL WATER.

THEN PULL TO 1450' AND MIX 90 SX CEMENT UNTIL CIRCULATED. PULLED TUBING AND TOPPED OFF

WITH 10 SX CEMENT. MIXED 15 SX CEMENT DOWN BACKSIDE PRESSURED TO 1500# AND HELD IN POSITION

AUG 30 1999

8-30-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J Maier (TECHNICIAN)

FORM CP-2/3

DATE 8-31-99

INV. NO. 60452

2