

To: **1 051376**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-7
API NUMBER **19-145-21,347.0000**

C NW SE, SEC. 6, T 21 S, R 15 W XX

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Lease Name Duford Well # 1

Operator: National Petroleum Reserves, Inc.
Name & Address 250 N. Rock Rd., Suite 340

County Pawnee 125.77

Wichita, KS 67206

Well Total Depth 3870 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 966

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 11 p.m. Day: 6 Month: 12 Year: 19 90

Plugging proposal received from Bill Alms
(company name) Emphasis Oil Operations (phone) 913-483-3518

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 957-989'

1st plug at 3820' with 50 sx cement, 2nd plug at 990' with 50 sx cement,

3rd plug at 400' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:15 a.m. Day: 7 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 3820' with 50 sx cement,

2nd plug at 990' with 50 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement. Water well plugged with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton!

(If additional description is necessary, use BACK of this form.)

INVOICED
(XXXX) (or net) observe this plugging.

DATE 1-7-91

Signed Richard M. Lacey
(TECHNICIAN)

INV. NO. 30367