

120183

12-14

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,443-0000

SE SE SE, SEC. 17, T 21 S, R. 11 W/E

330 feet from S section line

480 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Smith "B" Well # 6

Operator: Union Pacific Resources

County Stafford 113.75

Name & Address 1000 Louisiana, Suite 3000

Well Total Depth 3500 feet

Houston, TX 77002

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1988

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 14 Month: 12 Year: 1988

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3498' cemented w/100 sx cement Perfs at 3157-3295' (3 sets)
1st plug sand back to 3100' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 14 Month: 12 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3100' and dumped 5 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 50 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.
Pumping pressure 0-650 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1370' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DEC 19 1988

Signed Duane Rankin (TECHNICIAN)

DATE _____

INV. NO. 23412