

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-19877-00-00
Spot: SWNWSWNE Sec/Twnshp/Rge: 10-23S-13E
3340 feet from S Section Line, 2460 feet from E Section Line
Lease Name: YOUNG Well #: 1 OLD
County: GREENWOOD Total Vertical Depth: 1813 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1764		75 SX
SURF	10	33		31 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/13/2017 8:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: JIMTHWEATT Company: Phone: (620) 836-2000

Proposed Plugging Method: Cement Plug on bottom, perf at 850ft and 250ft, cement plug at 850ft, cement at 250ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 07/13/2017 11:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1577', pumped 15 sxs cement, pulled tubing to 861', pumped 15 sxs cement, pulled tubing to 246', pumped 25 sxs cement to surface, casing shot @ 860' & 250', gel spacers between cement plugs.

RECEIVED
KCC DIST # 3
JUL 17 2017
CHANUTE, KS

INVOICED
AUG 29 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

810 E 7th
PO Box 92
EUREKA, KS 67045
(620) 583-5561

AKJ 15-073-19877



Cement or Acid Field Report
Ticket No. **3433**
Foreman Steve Head
Camp Eureka, ks

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
7-13-17	1000	Young #1 old	10	23S	13E	Greenwood	KS
Customer			Unit #	Driver	Unit #	Driver	
Tremble & MacLuskey Oil LLC			104	Alan M			
Mailing Address			112	Tyson H			
P.O. Box 171			141	Karen M.			
City	State	Zip Code					
Gridley	Ks	66852					

Job Type PTA - Old well Hole Depth _____ Slurry Vol. _____ Tubing 2 7/8 1577'
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gall/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 2 7/8 Tubing. Break circulation w/ Fresh water.
Pump 300# Gel by 12:41. Spot 25 SKS AT 1577'
15 SKS AT 861'
25 SKS 246 to Surface Top well off.
Total 55 SKS 60/40 Pozmix 4% Gel

Job Sample

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	30	Mileage	3.95	118.50
C203	55 SKS	60/40 Pozmix Cement	13.75	758.75
C206	190 #	Gel 4%	1.20	228.00
C206	300 #	Gel Flush	1.20	360.00
C214	45 #	Hulls	1.45	65.25
C113	3 hrs	Robbl vac Truck	85.00	255.00
C224	3000 gal	CITY water	10.00/1000	30.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;"> 690 < 106.05 > # 2014.93 </div>			Sub Total	1973.00
			Sales Tax	147.98

Authorization Witness by Brian Title Co Rep Total 2120.98

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.