

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-007-22777-00-00  
 Spot: N2SESWSW Sec/Twnshp/Rge: 18-33S-10W  
605 feet from S Section Line, 4290 feet from E Section Line  
 Lease Name: NEWTON Well #: 1  
 County: BARBER Total Vertical Depth: 4715 feet

Operator License No.: 33168  
 Op Name: WOOLSEY OPERATING COMPANY, LL  
 Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
PROD	4.5	4664	3028	WITH 150 SX CMT
SURF	10.75	232		WITH 175 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2017 6:00 PM  
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
 Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4550' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 75 SX CMT. PLUG AT 40' WITH 35 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
 Date/Time Plugging Completed: 07/17/2017 7:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4550' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 260' WITH 75 SX CMT. 3RD PLUG AT 43' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4598	4626		

INVOICED  
AUG 30 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
 (TECHNICIAN)

RECEIVED  
 JUL 25 2017  
 KCC DODGE CITY

5A