

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Nowa County. Sec. 23 Twp. 29 Rge. (E) 16 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. 330 S. 330 N. from center of NW

Lease Owner Horndon Drilling Co.

Lease Name Dowell Well No. 1

Office Address Box 1565 Tulsa Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed..... 19.....

Application for plugging filed..... 9-10- 1942

Application for plugging approved..... 9-10- 1942

Plugging commenced..... 9-10- 1942

Plugging completed..... 9-10- 1942

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced?.....

Name of Conservation Agent who supervised plugging of this well Mr. Alexander

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 502.5 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from..... feet to..... feet for each plug set.

Hole filled with mud from 502.5 to 300. Hole bridged at 300. 15 sacks of cement on bridge. Hole filled with mud to 26 ft. Bridged and filled with cement to bottom of cellar.

PLUGGING  
FILE 29 28 86W  
BOOK 49-1244

STATE CORPORATION  
COMMISSION  
SEP 21 1942

9-21-42

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Horndon Drilling Co.  
Address Box 1565 Tulsa Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

..... (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Smith  
Tulsa, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 18 day of Sept, 1942  
Mary Lannon  
Notary Public.

My commission expires Nov 30-1944


Log of Dowell #1

Date spudded: August 11, 1942  
 Date set casing: Aug. 16, 1942 (8 5/8")  
 Date completed: Sept. 7, 1942

Loc: 23-28-16  
 Kiowa County, Kansas  
 Herndon Drilling Company

Total depth: 5025'

From	To	Formation	Remarks
0	11	Top Kelly Drive - Bottom cellar	
11	130	Surface soil and sand	
130	210	Sand	
210	310	Red bed	
310	340	Sand	
340	405	Shale and shells	
405	610	Shale and lime shells	
610	850	Shale and shells and sand	
850	890	Shale and sand	
890	950	Shale and Anhydrite	Run 912' 8 5/8" Casing set at 921' - cemented with 300 sacks cement
950	1365	Shale and shells and salt	
1365	1715	Shale and shells and salt	
1715	2190	Shale and shells	
2190	2340	Shale and lime	
2340	2400	Shale and lime	
2400	2495	Shale and lime	
2495	2610	Sandy lime and shale	
2610	2620	Shale	
2620	2640	Sandy lime	
2640	2755	Lime and shale	
2755	2815	Shale and lime	
2815	2880	Lime and shale	
2880	2990	Lime and shale	
2990	3100	Shale and lime	
3100	3190	Shale and lime	
3190	3305	Shale and lime	
3305	3420	Shale and lime	
3420	3460	Shale and lime	
3460	3470	Shale	
3470	3542	Lime	
3542	3575	Lime and shale	
3575	3655	Shale and lime	
3655	3715	Lime and shale	
3715	3790	Lime	
3790	3880	Lime	
3880	3975	Lime	
3975	4045	Lime and shale	
4045	4120	Shale	
4120	4160	Shale	
4160	4185	Shale	
4185	4217	Top K.C. Lime	
4217	4253	Lime and chert	
4253	4310	Lime with streaks of chert	
4310	4330	Lime and chert	
4330	4400	Lime	
4400	4445	Lime	
4445	4450	Lime	
4450	4455	Lime	
4455	4505	Lime	
4505	4545	Lime	
4545	4595	Lime and shale	
4595	4630	Lime and chert	
4630	4635	Lime and chert	
4635	4715	Chert and lime	
4715	4750	Chert and lime	
4750	4770	Lime and chert	
4770	4785	Lime and chert	
4785	4830	Lime and chert	
4830	4850	Chert	
4850	4885	Lime	
4885	4925	Shale and sand	
4925	4965	Shale and sand	
4965	4994	Shale and Dolomite	
4994	4995	Lime	
4995	5025	Lime	



PLUGGING  
 FILE SEP 22 1942 R 16W  
 BOOK PAGE 49 LINE 44

My Commission expires 10-18-45  
 Subscribed and sworn to before me this 14<sup>th</sup>  
 day of October, 1942  
 Colene [Signature] Notary

I hereby certify the foregoing to be a true and correct copy of the original driller's log on the Dowell #1  
 Isaac B. [Signature]