


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 6 Twp. 21 S Rge. (E) 15 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines C NE NW NE
Lease Owner Gulf Oil Corp.
Lease Name Leland Well No. 1
Office Address P. O. Box 661, Tulsa 2, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 27 1948
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced April 10, 1951
Plugging completed April 16, 1951
Reason for abandonment of well or producing formation Uneconomical to produce.

If a producing well is abandoned, date of last production November 21, 1950
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kansas
Producing formation Arbuckle Depth to top 3770' Bottom 3805' Total Depth of Well 3805' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	988'	None
				5 1/2"	3801'	3130'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with chat from 3805' to 3790' and dumped 5 sacks cement with bailer at 3790' which filled to 3769'. Mudded hole to 250', set rock bridge 250' to 240' and dumped 15 sacks cement on bridge. Mudded hole to 30' and capped with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to S. G. Sanderson
Address P. O. Box 661, Tulsa 2, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.
H. H. Wright (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. H. Wright*
P. O. Box 544, Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of April, 1951

My commission expires April 14, 1952

M. C. Council
Notary Public.

28-5091-s 8-50-10M

STATE CORPORATION COMMISSION

APR 19 1951

CONSERVATION DIVISION
Wichita, Kansas

4-19-1951

PLUGGING
FILE SEC 6 T 21 R 15 W
BOOK PAGE 74 LINE 36

State

15.145.01285.0000

WELL NO. 1 LEASE Leland COMPANY Gulf Oil Corporation A.F.E. 3618

DATE—DRILLING BEGAN 2-24-48 WELL COMPLETED 3-27-48 FIRST PRODUCTION 3-26-48

SAND RECORD Arbuckle 3770' - 3805' TOTAL DEPTH 3805'

INITIAL PRODUCTION OIL: 199 Barrels On State
WATER: 0 Barrels Physical test.
GAS: 3,770,000 Cu. Ft.

CASING RECORD

S-6 T-21S R-15W

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLG.	PULLED	LEFT IN
8-5/8"	32	10V	C	Smls	988'	435			988'
5-1/2"	14	8R	A	Smls	3801'	100			3801'

C									
NE									
NW									
SE									
Paynes									
County									
Kansas									

DISTANCE H: Top 5-1/2" casing is 6'6" below rotary bushing.

ELEVATION— 1986'

ACIDIZED: With 100 gallons 3-27-48.

FORMATION RECORD:

	FROM	TO
Sand and shale	0'	45'
Shale		740
Sand and shale		770
Sand		800
Shale		835
Shale and shells		905
Red bed and shells		982
Anhydrite		994
Shale and red bed		1105
Shale and shells		1915
Lime and shale		1955
Sandy lime		2185
Lime		2240
Lime and shale		2450
Lime		2495
Lime and shale		2840
Lime		2860
Shale and lime		2900
Lime and shale		3030
Lime		3195
Lime and chert		3245
Lime		3680
Lime and chert		3730
Lime and shale		3772
Lime		3805
TOTAL DEPTH		

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1951
CONSERVATION DIVISION
Wichita, Kansas

ED:IFM
5-3-48

PLUGGING
WELL NO. 1 LEASE Leland COMPANY
PAGE 74 LINE 36