

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County. Sec. 17 Twp. 21 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE

Lease Owner F. G. Holl

Lease Name Smith Estate Well No. 3

Office Address 6427 East Kellogg, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed _____ 19__

Application for plugging filed October 16 1970

Application for plugging approved _____ 19__

Plugging commenced October 25 1970

Plugging completed November 10 1970

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	290'	8 5/8"	290'	none
		0	3510'	4 1/2"	3510'	2429.66

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3500' and dumped 4 sacks of cement.

Pumped in 15 sacks of mud, 2 sacks of hulls and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of November 1970

My commission expires Feb. 10, 1971

George A. Meyer
Notary Public.

15.185.20222.0000

W E L L L O G

DATE COMMENCED: October 13, 1969
DATE COMPLETED: October 21, 1969

F. G. Holl
SMITH ESTATE #3
NE/4 NW/4 NE/4
Sec. 17-T21s-R11w
Stafford County, Kansas

0	-	183	Sand & Soil
183	-	530	Red Bed
530	-	552	Anhydrite
552	-	1465	Shale & Shells
1465	-	2140	Lime & Shale
2140	-	2463	Shale
2463	-	2635	Shale & Lime
2635	-	2990	Lime
2990	-	2995	Shale
2995	-	3009	Lime & Shale
3009	-	3022	Lime
3022	-	3118	Shale
3118	-	3135	Lime & Shale
3135	-	3356	Lime
3356	-	3407	Conglomerate
3407	-	3418	Chert
3418	-	3545	Conglomerate
3545			RTD

ELEVATION: 1776 K.B.

FORMATION TOPS

Anhydrite	530'
Heebner	2990'
Toronto	3009'
Douglas	3022'
Brown Lime	3118'
Kansas City	3135'
Base K.C.	3356'
Conglomerate	3391'
Chert	3407'
Conglomerate	3418'
RTD	3545'

SURFACE PIPE: Set 290' of new 8-5/8" 20# casing with 250 sacks cement.

PRODUCTION STRING: Set 4 1/2" casing @ 3510' with 125 sacks salt saturated pozmix.

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1970
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Larry Curtis of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Larry Curtis

Subscribed and sworn to before me this 29 day of October, 1969.

My Comm. Expires:
4-11-70

Dorothy M. Hague
Notary Public