


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 17 Twp. 21 Rge. (E) 11 (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NE/4
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Smith Well No. 1
Office Address 909 Palace Building, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 10 19 56
Application for plugging filed " " 19 "
Application for plugging approved " " 19 "
Plugging commenced " " 19 "
Plugging completed " " 19 "
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation Depth to top Bottom Total Depth of Well 3197 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole full of jell mud to 240',
1/3 sack hulls, plug and 20 sacks cement through
drill pipe. Jell mud to 35', 1/3 sack hulls,
plug and 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 710 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg employee of contractor
(employee of owner or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address)

SUBSCRIBED AND SWORN TO before me this 13 day of June, 19 56

My commission expires February 13, 1960.

Rose Fusery
Notary Public.

PLUGGING
FILE SEC. 17 T. 21 R. 11 W
BOOK PAGE 70 LINE 12

2-6-56

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.185 00330.0000

COMPANY Herman Geo. Kaiser-Francis Oil & Gas, Inc.

SEC. 17 T. 21 R. 11W

FARM Smith

NO. 1

LOC. NE NE NE

TOTAL DEPTH 3497

COMM. 5/30/56

COMP. 6/10/56


COUNTY Stafford

KANSAS

SHOT OR TREATED

CONTRACTOR H-30, Inc.

ISSUED



CASING

20	10	
15	8	255'
12	6	
13	5	

ELEVATION 1771 K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	195
Shale & Shells	1095
Anhydrite	1140
Shale, Shells & Red Bed	1250
Shale & Shells	1380
Shale & lime	1600
Shale, Lime & Salt	1740
Shale & Lime	3383
Shale, Lime & Chert	3430
Lime (Cherty) & Shale	3471
Lime, Shale & Chert	3497

FORMATION TOPS

HEEBNER	2990
BROWN LIME	3116
LANSING	3138
CONGLOMERATE	3382
SIMPSON SHALE	3425
SIMPSON SAND	3439
ARBUCKLE	3476

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *L.P. Springer*

STATE OF KANSAS
 COUNTY OF SEDGWICK

SS:

Subscribed and sworn to before me, a notary public, in and for said County and State this 12th day of June, 1956.

Rose Fussey
 Notary Public

My Commission expires February 13, 1960.

PLUGGING
 FILE SEC. 17 T. 21 R. 11W
 BOOK PAGE 70 LINE 12

RECORDATION DIVISION
 WICHITA, KANSAS