

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Barton County. Sec. 28 Twp. 16 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Duke Drilling Co.
Lease Name HITSCHMANN Well No. 5
Office Address Box 823 - Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 2 19 66
Application for plugging filed " " 19 66
Application for plugging approved " " 19 66
Plugging commenced December 2 19 66
Plugging completed " " " 19 66
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Locate well correctly on above Section Plat
Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation Depth to top Bottom Total Depth of Well 3400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS					CASING RECORD	
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 220'
1/4 Sack hulls - Plug - 25 sacks cement
Filled hole with heavy mud to 40'
1/4 sack hulls - plug - X Good Bridge - 10 sacks cement
2 sacks cement in Rat Hole

12-6-1966
RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor
Address

STATE OF KANSAS, COUNTY OF BARTON, ss.
L. O. CHUBB (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature]
Box 823 - Great Bend, Kansas (Address)
SUBSCRIBED AND SWORN to before me this 5th day of December, 1966.
[Signature]
Dorothy M. Hague Notary Public.
My commission expires April 11, 1970

W E L L L O G

DATE COMMENCED: November 26, 1966
 DATE COMPLETED: December 2, 1966

DUKE DRILLING COMPANY
 HITSCHMANN #5
 NE SW NE
 Sec. 28-16-12W
 Barton County, Kansas

ELEVATION: 1910 K.B.

0 - 75' Post Rock & Clay
 75 - 475' Shale & Sand
 475 - 813' Red Bed
 813 - 838' Anhydrite
 838 - 1550' Shale & Shells
 1550 - 1965' Shale & Lime
 1965 - 2540' Shale & Shells
 2540 - 3002' Lime & Shale
 3002 - 3006' Shale
 3006 - 3019' Lime & Shale
 3019 - 3032' Lime
 3032 - 3092' Shale
 3092 - 3110' Lime & Shale
 3110 - 3358' Lime
 3358 - 3382' Conglomerate
 3382 - 3400' Dolomite

FORMATION DATA

Anhydrite	813
Heebner	3003
Brown Lime	3092
Lansing	3110
Conglomerate	3358
Arbuckle	3382
R.T.D.	3400

SURFACE PIPE: Set 330' of
 8-5/8" casing with 200 sacks
 cement, 2% gel.

A F F I D A V I T

State of Kansas
 County of Barton) ss.

L. O. Chubb, of lawful age, does swear that the facts and
 statements herein contained are true and correct to the best of his
 knowledge.


 L. O. Chubb

Subscribed and sworn to before me this 5th day of December, 1966

My Comm. Expires:

April 11, 1970


 Dorothy M. Hague NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 6 1966
 CONSERVATION DIVISION
 WICHITA, KANSAS