


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Barton County. Sec. 28 Twp. 16 Rge. 12 N/W  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines  
100' NW SW SE SW  
Lease Owner Petroleum Energy, Inc.  
Lease Name FINGER Well No. 3  
Office Address 710 - One Twenty Bldg. Wichita, Ks.  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date Well completed 10-2 19 79  
Application for plugging filed 10-2 1979  
Application for plugging approved 10-2 1979  
Plugging commenced 10-2 1979  
Plugging completed 10-2 1979  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3385'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug set At 450' w/50 sacks cement thru Drill Pipe  
Middle Plug set at 240' w/25 sacks cement thru Drill Pipe  
Top Plug set at 40' w/1/2 sacks Hulls and 10 sacks cement  
2 sacks cement in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION

OCT - 9 1979

10-9-79

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.  
Leonard Williamson (employee of owner) or ~~(owner or operator)~~  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

(Address)

SUBSCRIBED AND SWORN TO before me this 5 day of October, 1979

Dorothy M. Hogue  
Notary Public.

My commission expires April 11, 1982

## DRILLERS' WELL LOG

DATE COMMENCED: September 25, 1979

DATE COMPLETED: October 2, 1979

Petroleum Energy, Inc.

FINGER # 3

100' NW of SW SE SW

Sec. 28 - T16 - R12W

Barton County, Ks.

0 - 200' Clay, Postrock, Sand  
 200 - 791' Shale, Shells, Red Bed  
 791 - 815' Anhydrite  
 815 - 1510' Red Bed & Shale  
 1510 - 2676' Shale & Lime  
 2676 - 2702' Lime  
 2702 - 2713' Shale  
 2713 - 2993' Lime  
 2993 - 2997' Shale  
 2997 - 3012' Lime & Shale  
 3012 - 3023' Lime  
 3023 - 3084' Shale  
 3084 - 3098' Lime & Shale  
 3098 - 3341' Lime  
 3341 - 3354' Lime & Shale  
 3354 - 3385' Dolomite  
 3385' RTD

ELEVATION: 1901 K.B.

## FORMATION DATA

Anhydrite	791
Howard	2676
Severy	2702
Topeka	2713
Heebner	2993
Toronto	3012
Douglas	3023
Br. Lime	3084
Kansas City	3098
Base K. C.	3341
Conglomerate	3350
Arbuckle	3354
RTD	3385

SURFACE PIPE: Set used  
 8 5/8" pipe, 28 # @ 248'  
 w/150 sacks 60/40 Pozmix,  
 2 % gel., 3 % cc.

## AFFIDAVIT

State of Kansas  
 County of Barton ) ss.

Leonard Williamson, of lawful age does swear and state that the facts and  
 statements herein contained are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 5 day of October, 1979

RECEIVED  
 STATE OF KANSAS  
*Deborah M. Hague*  
 Notary Public  
 OCT - 5 1979

My Comm. Expires: April 11, 1982

COME WA. OF JPM SIG  
 10/11/79