

MAGNOLIA PETROLEUM COMPANY
 A. Klug #1
 NW NE NW Section 31-16-12W

Drilling Commenced
 Drilling Completed

Casing Record:
 10-3/4" Set at 250' -
 Cemented w/200 Sax.

Surface Clay & sand	0	80
sand & shells	80	230
clay & shells	230	252
10-3/4" Csg. Set	250	
shale & shells	252	480
shale & shells	480	845
Anhydrite	845	875
lime	875	900
shale & shells	900	1135
shale	1135	1230
salt	1230	1470
shale & shells	1470	1595
lime broken	1595	1672
shale & lime shells	1672	1690
lime	1690	2030
lime & Pyrite iron	2030	2095
lime & shale	2095	2120
lime	2120	2135
shale & shells	2135	2350
lime & shale	2350	2685
broken lime	2685	3159
Top Lansing	3195	3412
Lansing	3195	3412
Top Conglomerate	3412	
Conglomerate	3412	3441
Top Arbuckle	3441	
Arbuckle lime	3441	3464

TD -SLM 3464

Plugged & Abandoned.

PLUGGING
 FILE REC 31-16-R12W
 BOOK PAGE 12 LINE 38

