

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Section plot grid for well location.

Locate well correctly on above Section Plot

Stafford County, Sec. 28 Twp. 21 Rge. 14 (E) (W) X
Location as "NE/CNW/SW" or footage from lines SW/NW/SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Smith "A-F" Well No. 1
Office Address 905 Century Plaza Wichita, Ks. 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed December 21, 1972
Application for plugging approved 19
Plugging commenced January 6, 1973
Plugging completed January 18 1973
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Contains data for casing sizes 8 5/8 and 4 1/2.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Removed 8 5/8" head and put on control head. Measured T.D. and dumped sand to 3750 ft. and 4 sacks cement. Shot casing at 3485 ft. Shot at 3280, 2800, 2400, 2100, 2000 and 1900 ft. Allied squeezed well with 2 sacks hulls, 15 gel and 100 sacks cement after pulling 56 jts. of 4 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION
JAN 22 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Eng., Inc.
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

CATHY MILLER
NOTARY PUBLIC
Barton County, Ks.

(Signature) James W. Rockhold
James W. Rockhold
Box 698 Great Bend, Ks. 67530
(Address)

Subscribed and sworn to before me this 19th day of January, 1973

My commission expires September 30, 1975

Cathy Miller
Cathy Miller Notary Public.

WELL LOG

15-185-11358.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 28 T. 21S R. 14W

FARM SMITH "AF" NO. 1


LOC. SW, NW, SW

TOTAL DEPTH 3830'

COUNTY STAFFORD CO., KANSAS

COMM. September 8, 1961 COMP. September 24, 1961

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 260' w/225 sax.
4 1/2" @ 3827' w/75 sax.

ELEVATION 1944' DF

PRODUCTION Simpson Sand

FIGURES INDICATE BOTTOM OF FORMATIONS

260	Surface soil , shale & sand
665	Shale & red bed
865	Red bed & shale
890	Anhydrite
1565	Shale & shells
1820	Shale & lime
3190	Lime & shale
3830	Lime
3830	T. D.

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1972
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 SMITH "AF" well.

Verne A. Morris

Subscribed and sworn to before me this 3rd day of October 19 61

My Commission Expires: April 14, 1963

Arthur J. Miles
NOTARY PUBLIC