


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 28 Twp. 21 Rge. 14 (W) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NE NE
Lease Owner Petroleum, Inc.
Lease Name Strickler Well No. 1
Office Address 100 Derby Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 4, 19 52
Application for plugging filed May 4, 19 52
Application for plugging approved May 4, 19 52
Plugging commenced May 4, 19 52
Plugging completed May 4, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	277'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 175' and set wooden plug at 175'. Cemented and displaced 15 sacks cement through drill pipe on top of plug at 175'. Mudded up to 35' and placed second wooden plug at 35'. Filled hole with 15 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
W. W. Fisher (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) WW Fisher

100 Derby Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of May, 19 52

My commission expires October 13, 1954 STATE CORPORATION COMMISSION

23-8390-s 6-51-20M

RECEIVED Notary Public

PLUGGING
FILE SEC 28 T 21 R 14
BOOK PAGE 14 LINE 13

MAY - 9 1952
CONSERVATION DIVISION

5-9-52

DRILLER'S LOG STRICKLER #1

Petroleum, Inc., Lease Owner

Section 28, Twp. 21S, Rge. 14W

Garvey Drilling Company, Contractor

Location: SE NE NE

Drilling Commenced: April 25, 1952

County: Stafford County, Kansas

Drilling Completed: May 4, 1952

Production: D & A

Casing Record: 8 5/8" @ 277' w/175 sax

R.T.D.: 3830'

Figures below indicate bottom of formation:

230	Sand & Shells
277	Shale & Shells
435	Shale, Sand & Red Bed
855	Red Bed
880	Anhydrite
1705	Shale & Shells
1795	Lime & Shale
2020	Lime
2840	Lime & Shale
3040	Shale & Shells
3135	Lime & Shale
3220	Lime
3295	Lime & Shale
3370	Lime
3416	Shale
3680	Lime
3700	Shale
3756	Viola & Conglomerate
3806	Shale
3830	Lime

Tops:

Heebner:	3299 (-1354)
Brown Lime:	3416 (-1471)
Lansing:	3426 (-1481)
Conglomerate:	3703 (-1758)
Viola:	3708 (-1763)
Simpson:	3755 (-1810)
Arbuckle:	3805 (-1860)

R.T.D. 3830'

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

PLUGGING			
FILE	SEC 28	T 21	R 14
BOOK	PAGE 18	LINE 15	BY <u>W. W. Fisher</u>

W. W. Fisher

STATE OF KANSAS :
 : SS:
 COUNTY OF SEDGWICK :

Subscribed to and sworn to before me, a Notary Public in said County and State, this 7th day of May, 1952.

VED
 NOTARY COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

Charlotte Friedman
 Notary Public

My commission expires: October 13, 1954.