


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 27 Twp. 21S Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines Center NE/4
Lease Owner Clay Newell
Lease Name Pile Well No. 3
Office Address Stafford, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned Oil Well
Date well completed _____ 19____
Application for plugging filed February 1, 19 62
Application for plugging approved February 1, 19 62
Plugging commenced February 1, 19 62
Plugging completed February 3, 19 62
Reason for abandonment of well or producing formation oil depleted to not
economical to operate
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lakamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3779 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	403'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole sanded to 3500 feet. 5 sacks of cement dumped with bailor. Pulled 2210 feet of 5-1/2 inch casing. Mudded hole to 400 feet. Set rock bridge from 400 to 390 feet. Dumped 20 sacks of cement on bridge. Mudded hole to 40 feet. Rock bridge to 30 feet filled hole with cement to base of cellar.

6-26-64

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1964

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Glenn & Smith Pipe Pulling Company
Address Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clay Newell

SUBSCRIBED AND SWORN TO before me this 25th day of June, 1964

My commission expires Sept 2, 1967 Dean L Newell Notary Public.

Ralph Glenn
Phone 449-R

INVOICE

Glenn & Smith Pipe Pulling Co.

15.185.10809.0000

R. E. Smith
Phone 882-R

Box 114
ELLINWOOD, KANSAS

Date 2 / 1 / 62

Sold To: CLAY NEWELL

Invoice No. 3

Well No. 3

Sec. 27 - 21 - 14

Lease Pile

1/30/62	Cleaning out collar, run at 3540' and run 5 sacks 3540' to 3500'.	5 hrs.	\$ 42.00
---------	---	--------	----------

1/31/62	Working 24" tension in 2997', 2900', 2775', 2195'; and started 5'	7 hrs.	49.00
---------	---	--------	-------

2/1/62	Mudded from 3500' to rock bridge 400' to 385' and run 3 sacks cement from 385' to 376'.	3 hrs.	21.00
--------	---	--------	-------

2/ 2/62	Bailed down water and run 17 sacks of cement from 376' to 325' mudded from 325' to 40' rock and 10 sacks of cement from 40' to base of cellar.	4 hrs.	28.00
---------	--	--------	-------

20 hrs @ \$ 7.00 per hr.	140.00
7 shots @ \$ 10.00 per hr.	70.00
2212' 5 1/2" @ .20 per foot	442.40
	\$ 652.40

PERMIT NO. 396
STATE PLUGGER: W. L. LaKamp

RECEIVED
STATE COMMISSION

APR 6 1962

CONSERVATION DIVISION

THANK YOU