

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH

			X

Locate well correctly on above
Section Plat

Stafford County. Sec. 27 Twp. 21 Rge. (E) 14 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE NE NE

Lease Owner. Crown Oil Company, Inc.

Lease Name. Ratzlaff Well No. 1

Office Address. P. O. Box 164, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole). D/A

Date well completed. October 20, 1950 19

Application for plugging filed. October 19 19.50

Application for plugging approved. October 19 19.50

Plugging commenced. October 19, 19.50

Plugging completed. October 20 19.50

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough

Producing formation. Depth to top. Bottom. Total Depth of Well 3820 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3820' to 210' filled with heavy rotary mud, and one plug set with fifteen sacks of cement, then filled to 40' with heavy rotary mud; then filled with one plug and ten sacks of cement to top of hole.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Crown Oil Company, Inc.
Address. P. O. Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

H. R. Buick, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

HILTON DRILLING COMPANY, INC.
(Signature) By: H. R. Buick
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 19th day of February, 1951

My commission expires June 13, 1951

Notary Public
Henry Pearson

21-6858-RS-2-47-6M
PLUGGING
FILE SEC 27 T 21 R 14
BOOK PAGE 37 LINE 22

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC. LOCATION: NE NE NE 27-21-14
 Contractor: HILTON DRILLING COMPANY, INC. ELEVATION: Stafford County, Kansas
 1935 K.B.
 FARM NAME: RATZLAFF No. 1
 COMMENCED: October 4, 1950
 COMPLETED: October 20, 1950

CASING USED: 8-5/8" at 243' with 200 sacks

Cellar
 Surface Clay, Sand & Gravel 95
 Sand and Clay 200
 Blue Shale 215
 Shale and Shells 265
 Sand 310
 Sandy Red Bed 365
 Sandy Red Bed 830
 Anhydrite 870
 Shale and Shells 1280
 Sandy Shale 1310
 Shale and Shells 1400
 Shale and Lime 1600
 Lime and Shale 1885
 Sand and Chert 1905
 Lime 1930
 Lime and Shale 2070
 Lime 2120
 Lime and Shale 2800
 Lime 2830
 Lime 2895
 Shale 2915
 Lime 2980
 Lime and Shale 3155
 Lime and Shale Gyp 3204
 Lime and Shale 3245
 Lime Shale 3293
 Lime 3500
 Lime 3662
 Lime and Chert 3771
 Cong. 3820
 Total Depth 3820

GEOLOGICAL TOPS

Heebner Shale 3282
 Brown Lime 3400
 Lansing (White) 3411
 Viola 3698
 Simpson Shale 3744
 Arbuckle 3793

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1951
 CONSERVATION

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

By W. R. Beuch

Subscribed and sworn before me this 19th day of February, 1951.

Henry Peacock
 Notary Public

My commission expires June 13, 1951.

PLUGGING
 FILE SEC-2712146
 BOOK PAGE 37 LINE 11