

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

AMENDED

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

API NUMBER 15-185-20,579.0000

LEASE NAME Devine

WELL NUMBER 1

2970 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 27 TWP. 21SRGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed 6/11/75

Plugging Commenced 9/25/89

Plugging Completed 9/27/89

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well W.I. (input)

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form if not, is well log attached? -

Producing Formation None Depth to Top - Bottom - T.D. 3708

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Water	3544	48	8 5/8	280	-0-
				5 1/2	3705	2635

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped 5 sxs cmt + sand from TD to 3500'. Shot pipe @ 2824' & 2635'. POOH.
Plugged surface w/4 hulls, 10 gel, 50 sxs cmt, 10 gel, 1 hull, & 100 sxs 60/40 6% gel.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
(Address) P. O. Box 21468, Tulsa, OK 74121

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN before me this 24th day of October, 19 89

CONSERVATION DIVISION
Wichita, Kansas

My Commission Expires 3-29-92

Judith E. Jewell
Notary Public

10-26-89

revised log
KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLING BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15.185.20579.0000

COMPANY Francis Oil & Gas, Inc.

SEC. 27 T. 21S R. 14W
 LOC. 50' S, 250' E of
 SW SE NW

FARM Devine


NO. 1

COUNTY Stafford

TOTAL DEPTH 3,708'
 COMM. April 23, 1975

COMP. April 30, 1975

SHOT OR TREATED
 CONTRACTOR H-30, INC.
 ISSUED



CASING

20	10		
15	5 8/8"	280' cemented w/250 sxs cement	ELEVATION 1,936' KB
12	6		
13	5 1/2"	3,707' cemented w/150 sxs cement	PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	220'
Shale	281'
Shale and Red Bed	818'
Anhydrite	865'
Shale	1,208'
Shale and Lime	1,800'
Lime and Shale	2,466'
Shale	2,705'
Shale and Lime	2,882'
Lime and Shale	3,670'
Lime and Chert	3,708'
Rotary Total Depth	3,708'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.


H-30, Inc.

Dean Britting
 Dean Britting

State of Kansas }
 County of Sedgwick } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 5th day of May, 1975.

Elsie Willison
 Elsie Willison - Notary Public



My Commission Expires:
 June 30, 1978

RECEIVED
 STATE CORPORATION COMMISSION

SEP 11 1989

CONSERVATION DIVISION
 Wichita, Kansas