

KANSAS

*74*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 13 1966

6-13-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum

Complete Address: 1740 Broadway, Denver, Colorado

Lease Name Keenan Well No. # B-2

Location SE NW SW Sec. 27 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3798'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:45PM Day 4th Month June Year 1966

The Above well was plugged as follows:

440' of 85/8" surface pipe, cemented with 350 sacks. 3797' of 5 1/2" long  
string, cemented with 125 sacks. Top perforation 3535'. Bottom of the hole  
was sanded to 3500', and cemented with 5 sacks, through the dump bailer.  
Hole was flowing with water, and a squeeze was necessary. 10 sacks of  
gel-mud and 80 sacks of cement was pumped in to the 8 5/8" surface pipe  
to a pressure of 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6-13-66  
INV. NO. 3389-W

Signed: Archie Elving  
Well Plugging Supervisor