

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name James M. Stewart

Complete Address: 820 Union Center Bldg., Wichita, Kansas

Lease Name Devine Well No. # 1

Location SE SE NW Sec. 27 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3781

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers Inc.

Address: Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:00PM Day 29th Month May Year 1964

The Above well was plugged as follows:

255' of 8 5/8" surface pipe, cemented with 225 sacks. 3778' of 4 1/2" long
string, cemented with 125 sacks. Plug back to 3770'. Top perferation
3537'. Plug was pushed to 3500', 10' rock bridge, and bottom of hole cem-
ented with 3 sacks. Fluid was up in the hole. Plug was pushed to 250',
with 10' of rock bridge. 5 sacks of cement and 5% calcium chloride, was
mixed in barrel and put on plug through dump bailer, and let set over-
night. Next morning hole bailed down, and 20 sacks cement was added to
plug. Hole was filled with mud to 40', with 10' of rock bridge, and cem-
ented with 10 sacks to base cellar. 3020' of 4 1/2" long string was recover-
ed from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/2/64
INV. NO. 9234-U