

15.185.19501.0001

Form CP-3  
Rev. 6-26-62

*14* KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Union Texas Petroleum  
Complete Address: 1740 Broadway, Denver, Colorado  
Lease Name Keenan Well No. # B-4  
Location NE NW SW Sec. 27 Twp. 21 Rge. 14 (E) (W)W  
County Stafford Total Depth 3876'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well X D & A       
Other well as hereafter indicated:       
Plugging Contractor: Forbes Casing Pulling, Inc.  
Address: Box 221, Great Bend, Kansas License No. 49  
Operation Completed: Hour 11:15AM Day 11th Month April Year 1966

The Above well was plugged as follows:

458' of 8 5/8" surface pipe, cemented with 350 sacks. 3814' of 5 1/2"  
long string, cemented with 125 sacks. All perferation were squeezed  
with 200 sacks of cement, bringing the top of the cement to 1500' in  
5 1/2" casing. 1300' of 5 1/2" long string was recovered from the hole. Bridge  
plug was pushed in fluid to 330', rock bridge from 330' to 310'. 5 sacks  
of cement was mixed in a barrel, and put on plug at 310', through the dump  
bailer, and let set over week end. Hole was bailed dry and 20 sacks of cem-  
ent was added to the plug. Hole was filled with mud to 40', rock bridge  
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Archie Elving*  
Well Plugging Supervisor

DATE 4/12/66

INV. NO. 3022-W