

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

5-6-1965
RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bovaird Supply Co 15-145-61165-0000
Complete Address: Box 897 Great Bend, Kans
Lease Name Schartz Well No. 3
Location NE NW SW Sec. 4 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4293
Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Apex Pipe Pulling & Sun Cementing Co

Address: Hoisington, Kans License No. 544

Operation Completed: Hour 11:30AM Day 4 Month 5 Year 65

The Above well was plugged as follows:

8 5/8" 311' circulated with cement - 5 1/2' 4292' with 150 sax cement.
Sand back to 4191' - set 4 sax cement with dump bailer - pulled 3367'
5 1/2" - pumped hole full heavy mud (.40 sax Gel), pumpe plug followed
by 100 sax cement - squeezed

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edson Peery*
Well Plugging Supervisor

DATE 5/9/65
INV. NO. 1113-W