

15009-05553-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 129-24

LOCATION CS/R-SW-SW

SEC. 36 TWP. 16 RGE. 11-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease A. F. Smith

Operator Mr. J. J. Lynn Address 1000 B. A. Long Bldg - N. City - Mo

Field _____ County Barton

Total Depth 3427 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 244 ft. Circulated with cement.
4 1/2" casing set at 3396 ft. Plugged back from bottom to
3390 ft with sand & chat - Dumped 3 sacks of cement
in the 4 1/2" casing at 3390 ft - Shot off & Pulled the 4 1/2" casing -
Mud to 244 ft - Rock Bridge & 15 sacks of cement at 244 ft
Mud to 30 ft - Bridge & 10 sacks of cement to the surface
Miller Casing Pulling Co - Plugging - Contractors -

RECEIVED

PLUGGING 22 1949
FILE SEC 36 T. 16 R. 11
BOOK PAGE 129 LINE 24

C. M. Stough
District Conservation Agent

Date 12-20-49

12-22-49