



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Thunderbird has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling & Petroleum Resources

Complete Address: Box 18407, Wichita, Kansas

Lease Name: Buerkle "B" Well No. 3

Location: "200' W of NE NE Sec. 8 Twp. 21 Rge. 33 ~~(E)~~ (W)

County: Finney Total Depth 4800' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Weber was instructed to plug the well as follows:

8 5/8" to 407' circulated w/ cement. Mud 4800' to 400'

Spot 35 sacks cement 400' to 300' Mud 300' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent