



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Radke of Garvey Drlg. Co. has this date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Oil Properties Co. Inc.

Complete Address: 915 Century Plaza Wichita, Ks

Lease Name: Neeland Well No. 1

Location: NE/SW/NE Sec. 32 Twp. 21s Rge. 14 (E)(W) W

County: Stafford Total Depth 3915 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:
471 ft 8 5/8 surface pipe cemented with 350 sacks. Fill hole
to 260 ft, plug, 1/2 sack hulls, 35 sacks cement through drill
pipe. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks cement to
surface. 2 sacks cement in rat hole. 2 sacks cement in
mouse hole.

Very truly yours,

J. Russell Biberstein
Conservation Division Agent