

KANSAS

P
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued September 14, 1967.

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Spector Pipe & Supply, Inc.

Complete Address: Box 169, Russell, Kansas 67665

Lease Name Cox "A" Well No. # 1

Location NE NE NE Sec. 32 Twp. 21 Rge. 14 (E) W (W) W

County Stafford Total Depth 3808'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Lynch Casing Pulling Company

Address: R. R. # 4, Great Bend, Kansas 67530 License No. 457

Operation Completed: Hour 11:15 AM Day 14th Month October Year 1967

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cemented with 175 sacks. 3807' of 5 1/2" long string,
cemented with 125 sacks. Bridge plug and sand to the top of the Kansas City at
3400', and cemented with 5 sacks, with cement from 3400' to 3360', cemented
through the dump bailer. 2994' of 5 1/2" long string was recovered from the hole.
Hole was squeezed. 10 sacks of Gel-Mud and 80 sacks of cement was pumped into
the surface pipe, through 5 1/2" nipple, with the braden head shut in, to a pressure
of 200 lbs., with the cement from 240' to the base of the cellar.

This cement was pumped by Lynch Casing Pulling Company

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/16/67
INV. NO. 6494-W