

15.185.11358.0001

Form CP-3
Rev. 6-4-68

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drlg Co Inc

Complete Address 905 Century Plaza Wichita, KS

Lease Name Smith A-F Well No. 1

Location SW/NW/SW Sec. 28 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3830

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 637

Operation Completed: Hour 5:30 PM Day 18 Month 1 Year 1973

The above well was plugged as follows:

260 ft 8 5/8 surface cemented with 225 sacks. 3827 ft 4 1/2 long string
cemented with 75 sacks. Top perf. 3765 ft. Sand to 3750 ft, 5 sacks
cement with bailer. Pulled 1900 ft 4 1/2. Pump 3 sacks hulls, 15 sacks
gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co Russell, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 1/24/73
INV. NO. 6891-W