


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 21 Twp. 21S Rge. 23 (W) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE NW SE
Lease Owner Atmar Drilling Co., and John Lindas Oil, Inc.
Lease Name Folkerts Well No. 1
Office Address 1314 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 4, 1953
Application for plugging filed July 4, 1953
Application for plugging approved July 4, 1953
Plugging commenced July 4, 1953
Plugging completed July 4, 1953
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale & Sand	70'	0	20'	10-3/4"	20'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Filled hole with mud to 300'. Set plug and 20 sacks cement. Filled hole with mud to 40' and set plug with small sack of hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor John Lindas Oil, Inc.
Address 1314 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. M. Callaway (employee of owner) or (owner or operator) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *F. M. Callaway*
1314 Union National Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1953.

My commission expires October 8, 1955.

Edward W. Atien
STATE CORPORATION COMMISSION Notary Public.



JUL 7 1953 7-7-53
CONSERVATION DIVISION
Wichita, Kansas

DRILLING LOG

Lease Operator: John Lindas Oil, Inc.
 1314 Union National Bank Bldg.
 Wichita 2, Kansas

County: Hodgeman
 Location: C. SE/4 NW/4 SE/4
 Section: 21-21S-23W
 Elevation: 2375' DF
 2373' GR.

Well: Folkerts No. 1

Rotary Total Depth: 4603'
 Commenced: June 3, 1953
 Completed: July 4, 1953
 Casing: 10-3/4" @ 204' with
 150 sacks of cement
 and 2 sacks of cal-
 cium chloride.

Contractor: John Lindas Oil, Inc.
 1314 Union National Bank Bldg.
 Wichita 2, Kansas

FIGURES INDICATE BOTTOM OF FORMATION

0	to	80	Shale and Sand
80		120	Blue Shale and Shells
120		360	Shale and Shells
360		380	Red Rock
380		775	Shale
775		925	Red Rock
925		1070	Red Bed
1070		1355	Sand
1355		1590	Shale and Shells
1590		1620	Anhydrite
1620		1970	Shale and Shells
1970		2150	Shale
2150		2330	Shale and Shells
2330		2375	Shale
2375		2430	Shale, Shells and Lime Streaks
2430		2550	Shale
2550		2630	Shale and Shells
2630		2685	Shale
2685		2820	Shale and Shells
2820		3690	Lime and Shale
3690		3790	Lime
3790		3930	Lime and Shale
3930		4030	Lime
4030		4085	Lime and Shale
4085		4120	Lime
4120		4160	Lime and Shale
4160		4560	Lime
4560		4603	Mississippi Lime
		4603	T.D.

STATE OF KANSAS)
 : ss
 COUNTY OF SEDGWICK)

RECORDED
 STATE OF KANSAS
 COUNTY OF SEDGWICK
 JUL 10 1953
 EDWARD W. WIENS
 Notary Public

I, the undersigned, being duly sworn on oath, depose and state that the above statement and log is a true and accurate record of the well drilled by John Lindas Oil, Inc., at the location above described.

John Lindas

Subscribed and sworn to before me this 6th day of July, 1953.

Edward W. Wiens
 Notary Public

My Commission Expires: October 8, 1955.

21-21-23W
 112-94