

STATE OF KANSAS
STATE CORPORATION COMMISSION
J. S. Market, Room 2078
Chlta, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.083.20484.0000
Drld'd 8-76

LEASE NAME Folkerts

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 21 TWP. 21S RGE. 23W (E) or (W)

COUNTY Hodgeman

Date Well Completed

Plugging Commenced 8-16-99

Plugging Completed 8-16-99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P.O. Box 97 Ellinwood, Kansas 67526

PHONE(S) (316) 564-2578 OPERATORS LICENSE NO. 5131

Character of Well Oil

(Oil, Gas, O&A, SHD, Input, Water Supply Well)

Is plugging proposal was approved on (date)

 (KCC District Agent's Name)

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4553'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	329'	None
				4-1/2"	4539'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each section.
Ran 2" tubing down 4-1/2" casing to 4350', pumped 50 sks. cement, pulled upto 3966',
pumped 40 bbls. water w/30 sks. gel, pulled upto 1440' and circulated 85 sacks of
cement to top of hole, pulled rest of tubing out. Tied onto 8-5/8" surface pipe and
pumped 15 sks. cement to 250# pressure. Plugging Complete.
60/40 pos. 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1999
SUBSCRIBED AND SWORN TO before me this 18th day of August, 1999

CONSERVATION DIVISION
Wichita, Kansas

Irene Herzberg
Notary Public

My Commission Expires:



Form 09
Revised 05/99