


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 4 Twp. 23 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW

Lease Owner The Bovaird Supply Company

Lease Name Welch Well No. 4

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 3-25-65 19

Plugging completed 4-12-65 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4303 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	None
				5-1/2"	4301'	2730'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4260', sanded hole to 4230' and dumped 4 sacks of cement @ 4230' with dump bailer. Pulled 5 1/2" casing and pumped in 40 sacks of gel mud. Pumped in 95 sacks of cement and capped well with 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

APR 23 1965

4-23-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner/representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1965

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

15-145-0170-0000

ROONEY, SIEGFRIED & THOMAS

D. B. Welch, Well #4
SE SE SW Sec. 4-23S-17W
Pawnee County, Kansas

Casing Record:
8 5/8" @ 278' w/ 200 sx.
5 1/2" @ 4302' w/ 150 sx.

Commenced: October 21, 1955
Completed: November 4, 1955

Elevation: 2084 D. F.

LOG

Sand & surface clay	0 - 100
Red Beds	100 - 225
Shale	225 - 278
Shale & Shells	278 - 580
Sand Dakota	580 - 780
Red Beds & Shale	780 - 1120
Anhydrite	1120 - 1150
Shale & Shells	1150 - 1560
Lime & Shale	1560 - 2260
Lime	2260 - 2370
Lime & Shale	2370 - 2465
Lime	2465 - 2725
Lime & Shale	2725 - 3200
Lime	3200 - 3205
Lime & Shale	3205 - 3280
Lime	3280 - 3520
Lime & Shale	3520 - 3670
Lime	3670 - 4197
Cherty Conglomerate	4197 - 4303 RTD

I hereby certify that this log is true and correct to the best of my knowledge and belief.

JAYHAW DRILLING CO., INC.

By *John M. Linn*

Sworn and subscribed to before me
this 7th day of November, 1955.

Allen P. Denton
Notary Public

My Commission Expires: August 13, 1957

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1965
CONSERVATION DIVISION
Wichita, Kansas