

15-145-01168-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 4 Twp. 23 Rge. 17 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner The Bovaird Supply Company
Lease Name Welch Well No. 2
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-3-65 _____ 19____
Plugging completed 4-12-65 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4309 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	4308'	3442'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4248', sanded hole to 4230' and dumped 4 sacks of cement @ 4230' with dump bailer. Pulled 5 1/2" casing and pumped in 40 sacks of gel mud. Pumped 95 sacks of cement and capped well with 5 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

APR 23 1965

4-23-65
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of April, 19 65

Milton J. Volin
Notary Public.

My commission expires May 20, 1968

ROONEY, SIEGFRIED & THOMAS OIL CO.

15-145-01168-0000

Welch #2
SW SW SW Sec. 4-23S-17W
Pawnee County, Kansas

Casing Record:
8 5/8" @ 255' w/225 sx
5 1/2" @ 4305' w/120 sx

Commenced: August 7, 1955
Completed: August 20, 1955

Elevation: 2069 R.B.

LOG

Sand	0-25
Shale & shells	25-365
Red Beds	365-530
Sand	530-610
Shale, shell & sand	610-920
Red Beds & shale	920-1075
Anhydrite	1075-1110
Shale & shells	1110-1390
Shale, shells & salt	1390-1700
Shale & Shells	1700-1920
Lime, shale & shells	1920-2075
Lime & shale	2075-2275
Shale & lime	2275-2420
Lime & shale	2420-3090
Shale & lime	3090-3395
Lime	3395-3490
Lime & shale	3490-3720
Lime	3720-3780
Lime & shale	3780-3825
Lime	3825-4107
Lime & shale	4107-4210
Shale (cherty)	4210-4232
Shale (Kinderhook), cherty cong.	4232-4295
Conglomerate & Viola	4295-4306 RTD

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1955
CONSERVATION DIVISION
Wichita, Kansas

Correction 4306 = 4309 TD

DST #1 4156' to 4185' open 45 min. closed in 1 hr,
gas in 4 min., oil in 24 min. BHP 1190#
IFP 780# FFP 780#.

DST #2 4193' to 4210' open 30 min. weak blow. closed in
1 hr. Rec 20' mud BHP & FFP 0#.

I hereby certify that this log is true and correct to the best of my knowledge and belief.

JAYHAWK DRILLING CO., INC.

By John M. Little

Sworn and subscribed to before me
this 24 day of August, 1955.

Allen P. Deaton
Notary Public

My commission expires: Aug 13, 1957