

5-145-01166-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Pawnee County, Sec. 4 Twp. 23S Rge. 17W (E) (W) #
Location as "NE/CNW/SW" or footage from lines Nw./Sw/Sw.
Lease Owner Bovaird Supply.
Lease Name A.W. Schartz. Well No. #4
Office Address Box 897 Great Bend Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil.
Date well completed 11/19 1955
Application for plugging filed 3/1 1965
Application for plugging approved 3/10 1965
Plugging commenced 3/12 1965
Plugging completed 4/12 1965
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production 1/1 1965
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty.
Producing formation Mississippian Chat. Depth to top 4250 Bottom 4265 Total Depth of Well 4265 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2	4264	2637

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Sanded 5-1/2 Oil string from 4265 to 4190 mixed and dumped 4 sx. cement on sand bridge.
Squeezed well through 8-5/8 csg. with Sun Cementing pumped 40 sx. gell and 100 sz. Cement. to top of 8-5/8 csg.

RECEIVED
STATE CORPORATION COMMISSION
6-9-1965
JUN 9 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Apex Casing Pulling Company.
Address 739 East 2nd Hoisington Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ben Thompson
739 East 2nd Hoisington Kan
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1965

My commission expires Jan 8, 1968
Jacqueline Ochs
Notary Public.

15-145-01166-0000

ROONEY, SIEGFRIED & THOMAS

A. W. SCHARTZ No. 4
SE NE SW; Sec. 4-23S-17W
Pawnee County, Kansas
(Garfield Pool)

Contractor: Jayhawk Drilling Company

Drillers: E. L. Herbel
R. L. Barr
O. L. Sanders

Tool Pusher: Bill Little

Spudded: 8:20 PM. 11-5-55

Surface Csg: Ran 13 joints 8-5/8" - 32# csg. @ 249' with 200 sacks cement.
Plug down @ 4:20 AM., 11-6-55. Cement Circulated.

Oil String: 5-1/2" csg. @ 4264'.

Scratchers: 4165 to 4200; 4212 to 4215; 4219 to 4224; 4229 to 4234; 4237 to 4243.

Centralizers: 4050; 4140; 4200; 4260

Shoe Joint:

Zero:

GEOLOGICAL REPORT

1 Samples each 5 feet and 1 foot drilling time were taken for this well
from 3550 feet to RTD (4265)

The following data compiled through sample examination and Welox
log correlation.

ALL MEASUREMENTS ARE TAKEN FROM ROTARY BUSHING.

Elevation: 2065 K. B.; 2063 D. F.

<u>Formation</u>	<u>Depth</u>	<u>Sub-Sea</u>	<u>Thick</u>	<u>Source</u>
Anhydrite	1100 to 1125	+965	25'	Driller
Heebner	3610	-1545	4'	
Douglas	3640	-1575		
Brown Lime	3718	-1653		
Lansing-Kansas City	3724	-1659		
Shaley Conglomerate	4138	-2073		
Cherty Conglomerate	4167	-2102		
Viola	4245	-2180		
R. T. D.	4265	-2200		
5-1/2 Casing	4264	-2199		

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1965

CONSERVATION DIVISION
Wichita, Kansas