


WELL PLUGGING RECORD 15-45-01165-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 4 Twp. 23S Rge. 17W (E) (W)
Location as "NE/CNW%SW%" or footage from lines. Ne/Nw/Sw
Lease Owner Bovaird Supply.
Lease Name A. W. Schartz Well No. #3
Office Address Box 897 Great Bend Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 10/27 1955
Application for plugging filed 3/2 1965
Application for plugging approved 4/1 1965
Plugging commenced 4/2 1965
Plugging completed 5/4 1965
Reason for abandonment of well or producing formation Dry.

If a producing well is abandoned, date of last production 1/1 1965.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty.
Producing formation Mississippian Chat. Depth to top 4270 Bottom 4274 Total Depth of Well 4275 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5-1/2	4275	3363

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Sanded Back 5-1/2 Oil string from 4275 to 4120 Mixed and dumped 4 sx. cement on sand bridge.
Squeezed well through 8-5/8 csg. with 40 sx. gell and 100 sx. cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Apex Casing Pulling Company.
Address 739 East 2nd Hoisington Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Thompson
Hoisington Kan 739 East 2nd
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1965

My commission expires Jan. 8, 1968

Geneva Deh
Notary Public.

15-145-61165-0000

NE NW SW
4-23-17W

Rooney, Siegfried, & Thomas

The following is a Sample Analysis Report and Drilling Time Log on your No. 3 A.W. Schartz, Garfield Pool, Pawnee County, Kansas.

All formation tops and porosity zones were determined from sample analysis and time log interpretations and are corrected to the rotary bushing measurements.

Samples were examined from 3550' to total depth. The well was under geological supervision from 4100' to total depth/

WELL DESCRIPTION

Operator:	Rooney, Siegfried & Thomas	Commenced Drilling:	9-19-55
Farm:	A.W. Schartz	Completed	" 10-5-55
Well no. :	3	Casing :	8 5/8" @ 311'
Location:	NE NW SW		w/225 sacks
	4-23-17W		5 1/2" @ 4274'
Elevation:	2061 D.F.		w/150 sacks
	2063 K.B.	Contractor :	Jayhawk Drilling

FORMATION TOPS

HEEBNER	3595 (-1532)
BROWN LIME	3710 (-1647)
LANSING KANSAS CITY	3718 (-1655)
CONGLOMERATE SHALEY	4133 (-2070)
" CHERTY	4161 (-2098)
VIOLA	4254 (-2191)

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1965

CONSERVATION DIVISION
Wichita, Kansas