

15-145-6116-0500


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 4 Twp. 23 Rge. 17 (E) 17 (W)

Location as "NE/CNWxSWx" or footage from lings NW SE NE
Lease Owner Clark Knight
Lease Name Ewing Well No. 3
Office Address Box 969, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed 7-13 19 62
Application for plugging approved _____ 19____
Plugging commenced 7-14 19 62
Plugging completed 8-12 19 62
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4246 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	170'	none
				5 1/2"	4245'	2402'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top Perforation @ 4156'

Sanded hole to 4140'-dumped 5 sks cement-
pulled casing-pumped 15 sks mud and 75 sks
cement in surface casing.

RECEIVED
STATE CORPORATION COMMISSION

OCT 17 1962

10-19-62

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Co. License # 236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Clark Knight Drg. Co; Inc.
(Signature) _____ President
Box 969, Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of Oct, 19 62

Belle Myers
Notary Public.

My commission expires 8-14-65

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


15-145-01161-0000

Company: CLARK KNIGHT DRILG. Co. *done*
 Farm: Ewing No. 3

SEC. 4 T. 23 R. 17W
 NW SE NE

Total Depth. 4245'
 Comm. 2-27-56 Comp. 5-11-56
 Shot or Treated.
 Contractor.
 Issued. 8-4-56

County Pawnee
 KANSAS



CASING:
 10 3/4" 175'
 5 1/2" 4244'

Elevation. 2058 RB
 Production. 306 BOPD

Figures indicate Bottom of Formations.

surface-clay=	170
shale-shells	335
shale-red rock	545
sand	640
shale-shells	975
sand-shells	1026
shale-shells	1085
Anhydrite	1098
shale-shells	1900
shale-lime	2185
lime	2255
lime-shale	3215
lime	3610
lime-shale	3710
lime	4046
lime-shale	4160
sdv shale	4175
Conglomerate	4237
lime Viola	4245
Total Depth	

TOPS: Scout	
Anhydrite	1085
Heebner	3581
Toronto	3597
Douglas	3610
Brwn lime	3688
Lansing	3695
B/Kansas City	3974
Cherokee shale	4105
Cherokee sand	4112
Conglomerate	4125
Mississippi	4192
Kinderhook	4225
Viola	4230

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 19 1962
 CONSERVATION DIVISION
 Wichita, Kansas