


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 4 Twp. 22 Rge. (E) 17 (W)
 Location as "NE/CNW/SW" or footage from lines SE SE NE
 Lease Owner Fender Pipe & Supply
 Lease Name Ewing Well No. 1
 Office Address Box 302, Russell, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Oil
 Date well completed 19____
 Application for plugging filed 19____
 Application for plugging approved 19____
 Plugging commenced 7-23 19 62
 Plugging completed 8-11 19 62
 Reason for abandonment of well or producing formation _____
 If a producing well is abandoned, date of last production 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4238 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	245'	none
				5 1/2"	4237'	1574'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top Perforation 4147'

Sanded hole to 4130'-dumped 5 sks cement-pulled casing-pumped 15 sks mud and 75 sks cement in 8 5/8" surface casing.

RECEIVED
STATE CORPORATION COMMISSION
9-19-1962
SEP 19 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor R & D Casing Pulling Co. License # 236
 Address Box 572 Hutchinson, Kansas

STATE OF Kansas COUNTY OF Russell, ss.
Allen J. Fender (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen J. Fender
Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 1962.

My commission expires May 26, 1963 Ruth Phillips Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


15-145-01159-0000

Company- CLARK KNIGHT DRILLING CO.
Farm- Ewing No. 1

SEC. 4 T. 23 R. 17W
SE NE NE

Total Depth. 4237'
Comm. 12-3-54 Comp. 12-16-54
Shot or Treated.
Contractor.
Issued. 7-8-56

County Pawnee
KANSAS



Elevation. 2056'

Production. 1,024,000 Gas

Figures indicate Bottom of Formations.

surface	40
sand, shale	244
shale, shells	525
sand	630
shale, shells	1078
anhydrite	1103
shale, shells	1725
shale, lime	1900
lime, shale	3618
lime	4110
sdv lime, shale	4127
Viola	4142
Conglomerate	4237
Total Depth	

Tops:	
Heebner	3587
Toronto	3605
Brown Lime	3685
Lansing	3691
Cherokee	4107
Mississippi	4126
Viola	4231

DST #1 4112-27, rec. 120' slightly gas cut mud

DST #2 4127-58, oil to surface in 30 min.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1963

CONSERVATION DIVISION
Wichita, Kansas