

15-145-01158-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas


WELL PLUGGING RECORD

Pawnee County. Sec. 4 Twp. 23 Rge. 10 (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NW/SW/NE
Lease Owner Drilling And Exploration Company
Lease Name Ewing Well No. 2
Office Address Exchange Bank Bldg., Dallas, Texas

Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11-24 19 61
Plugging completed 12-8 19 61
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4263 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	None
				5 1/2"	4261'	3189'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 4175'
Top Perforation @ 4166'

Sanded to 4150' - dumped 5 sks cement - pulled casing - pumped 20 sks Gel Mud and 50 sks cement into surface casing.

Good
1-3-62

JAN 3 1962

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License # 236
Address Box # 572, Hutchinson, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jack Shear (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Drilling And Exploration Company
By Jack Shear
701 Ur Natl. Bldg. Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 19 61

My commission expires September 24, 1962
Maxine Johnson
Maxine Johnson Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY
15-145-01158 0000

Company- DRILLING & EXPLORATION CO., INC.
Farm- Ewing No. 2

SEC. 4 T. 23 R. 17W
NW SW NE

Total Depth. 4263
Comm. 12-8-55 Comp. 12-20-55
Shot or Treated.
Contractor. Birmingham-Bartlett Drlg Co.
Issued. 11-10-56

County Pawnee
KANSAS



CASING:

8 5/8" 248' cem w/200 sx.
5 1/2" 4261 1/2' cem w/150 sx.

Elevation. 2088

Production. 60 BOPD

Figures indicate Bottom of Formations.

sand, clay	190
shale	248
shale, sand	450
clay, shale, sand	1110
anhydrite	1135
shale, shells	1930
lime, shale	2345
lime	2445
shale, lime	2680
shale, shells	2805
shale, lime	2940
shale, shells	3090
shale, lime	3665
shale into lime	3745
shale, lime	3860
lime	3951
lime, shale	4015
lime	4075
lime, shale	4127
shaley Congl.	4172
conglomerate	4244
shale, lime	RTD 4263
Total Depth	

Tops: Scout	
Anhydrite	1110
Heebner	3609
Brown lime	3715
Lansing	3723
Conglomerate	4130
Viola	4256