


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 4 Twp. 23 Rge. 17 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE SE NE NW -
Lease Owner Sunray Mid-Continent Oil Co.
Lease Name V. Davis #1 Well No.
Office Address Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 28 19 55
Application for plugging filed May 26 19 58
Application for plugging approved May 27 19 58
Plugging commenced 6-5-58 19
Plugging completed 6-9-58 19
Reason for abandonment of well or producing formation Reached economic limit

If a producing well is abandoned, date of last production June 1, 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4280 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	288'	none
				5-1/2"	4274'	3228'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4170' and found it open.
Filled w/sand to 4138' and ran 5 sacks of
cement with dump bailer. Pulled 5 1/2" casing.
Had Halliburton squeeze well with 11 sacks
of gel mud and 75 sacks of cement.
Capped w/5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
N. E. Montgomery (employee of owner) or (owner or agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *N. E. Montgomery*
Box # 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 58

My commission expires 9-27-58
Thomas V. Duggs Notary Public.

JUN 20 1958
CONSERVATION DIVISION
6-20-58
PLUGGING
FILE SEC 4 T. 23 R. 17W
BOOK PAGE 103 LINE 14

VI 2 4 6

... ..

... ..

... ..

... ..

... ..

... ..

...

... ..

... ..

... ..

...

...

... ..

VI

RECEIVED
 V 19 1958
 Sunray Mid-Continent Oil Company
 KANSAS DISTRICT OFFICE



Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
March 15, 1955

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: February 26, 1955
Drilling Completed: March 14, 1955

V. Davis #1 SE/4-NW/4
Section 4-23S-17W,
Pawnee County, Kansas.

DRILLERS LOG

Sand	0-30
Shale	30-60
Shale & Sand	60-160
Shale & Shells	160-550
Sand	550-610
Shale & Shells	610-1090
Anhydrite	1090-1120
Shale & Shells	1120-1950
Shale & Lime	1950-2040
Lime & Shale	2040-2200
Lime	2200-2720
Lime & Shale	2720-3275
Broken Lime & Shale	3275-3370
Lime & Shale	3370-3425
Lime	3425-3515
Lime & Shale	3515-3675
Shale	3675-3708
Lime	3708-4015
Lime & Chert	4015-4075
Lime & Shale	4075-4114
Conglomerate	4114-4256
Viola	4256-4280 T.D.

I, Frank E. Stickle, hereby certify the above to be a true and complete Drillers Log of Sunray Oil Corporation's V. Davis #1 SE/4-NW/4, Section 4-23S-17W, Pawnee County, Kansas.

Frank E. Stickle
Frank E. Stickle

William T. Bonham
Notary Public

February 13, 1956
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1958

CONSERVATION DIVISION
Tulsa, Kansas

PLUGGING
FILE SEC. 4 T. 23 R. 17W
BOOK PAGE 103 LINE 14