

15-009-00973-0000

NORTH

A 4x4 grid with a small circle in the second row, second column.

**Locate well correctly on above
Section Plat**

Barton County, Sec. 36 Twp. 16S Rge. 11 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines S $\frac{1}{2}$ SE NW

Lease Owner J. J. Lynn

Lease Name Frank R. Kraft Well No. 1

Office Address.....1000 R. A. Long Bldg., Kansas City, Mo.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed.....11-21-41.....19.....

Application for plugging filed.....8-30-50.....19.....

Application for plugging approved.....8-30-50.....19.....

Plugging commenced 8-29-50 19

Plugging completed.....8-29-50.....19.....

Reason for abandonment of well or producing formation.....Non-Production.....

#####

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-

.....menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well..... C. D. Stough

Producing formation.....**Arbuckle**..... Depth to top.....**3340**..... Bottom.....**3370**..... Total Depth of Well.....**3370**..... Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Lane Well plug set at 3250!

Perforated K.C. from 3236' to 3228'

Squeezed off at 1150!.

Cemented to top of hole with 400 sacks of cement inside and out.

Halliburton plug set 25' and 5 sacks cement at top of hole

Cement top cap and bull plug at top.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....J. J. Lynn

Address..... 1000 R. A. Long Bldg.
..... Kansas City, Missouri

STATE OF Kansas, COUNTY OF Sedgwick, ss.
A. B. Allen (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).

1717 Garland, Wichita, Kansas

SUBSCRIBED AND SWORN to before me this 30th day of August, 1950 1950

My commission expires.....My Commission Expires Jan. 31, 1954

-22-7377-8

4-49-10M

Conservation-Div.

AUG 30 1950

STATE CORPORATION
COMMISSION
KANSAS

Notary Public.

WELL LOG

15-009-00973-0000

F. Kraft New Well # 1

Company

Location

H. M. Williams Drilling Co.
Wichita, KansasC S $\frac{1}{2}$ SE NW
36-16-11 W Barton CountyDrilling began 11-11-41
Well completed 12-5-41

Shale & shells	150	
shale & sand	195	
sand	230	253' of 10" casing
shells & shale	675	cemented with 140 sacks
anhydrite	927	
shale & shells	1120	
shale & salt streaks	1370	
shale & shells	1470	
broken lime	1520	
shale & shells	1580	
broken lime	1685	
lime & shale	1910	
lime	1970	
lime & shale	2120	
shale	2168	
sand	2185	
broken lime & shale	2220	
shale & shells	2520	
lime & shale	2675	
lime	2882	
shale & lime	3051	
lime	3221	slight oil stain 3204-21
lime & shale	3236	
broken lime & shale	3287	
lime	3311	
lime & shale	3348	3355' of 5" casing
lime	3370	cemented with 250 sacks
		cored from 3348 to 3370
	3370	acidized with 2000 gallons
		544 bbls per day
		gravity of oil 43.2 at 60°

T. D.

RECEIVED

Conservation Div.

AUG 30 1950

STATE CORPORATION
COMMISSION
KANSAS