


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 36 Twp. 16S Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE NW NW

Lease Owner Bankoff Oil Company
Lease Name Kraft Well No. 2
Office Address Drawer 2479, Tulsa, Okla. 74101
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 11-28 1978
Application for plugging filed 11-28 1978
Application for plugging approved 11-28 1978
Plugging commenced 11-28 1978
Plugging completed 11-28 1978

Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3385'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1978
CONSERVATION DIVISION
Wichita, Kansas


Hole plugged w/ 50-50 Pozmix
50 sks. @ 400'
10 sks. @ 40'
2 sks. in rathole
By Sun Cementing
Job completed @ 10:00 p.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company
P. O. Box 1389, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.
Allen Drilling Company (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Dale Smith
P. O. Box 1389, Great Bend, KS 67530
(Address)



SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 78
Notary Public.

DRILLER'S WELL LOG

DATE COMMENCED: 11-22-78
DATE COMPLETED: 11-28-78

Bankoff Oil Company
Kraft #2
SE NW NW, Sec. 36-16S-11W,
Barton County, Kansas

ELEVATIONS 1903' K.B.
1898' G.L.

FORMATION DATA

707- 736' Anhydrite
2689-2945' Lime
2945-2950' Shale
2950-2962' Lime
2962-3042' Lime
3042-3056' Lime and Shale
3056-3329' Lime
3329-3346' Lime and Shale
3346-3385' Shale, Lime, Chert and Sand
3385' RTD

Anhydrite 707
Topeka 2689
Heebner 2945
Toronto 2962
Brown Lime 3042
Lansing 3056
Base Kansas
City 3329
Conglomerate 3346
RTD 3385'

SURFACE PIPE:

Ran 9 Jts. Used 28# 8 5/8" Casing.
Tally 352'. Set 355' w/200 sks.
60-40 Pozmix, 2% Gel, 3% c.c.
By Sun Cementing. Plug down @ 9:15.
Cement did circulate.

PLUGGING:

Hole Plugged w/ 50-50 Pozmix
50 sks. @ 400'
10 sks. @ 40'
2 sks. in the rathole
By Sun Cementing.
Job completed @ 10:00 p.m.

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale Smith

Subscribed and sworn to before me this 30th day of November 1978.



RECEIVED
STATE CORPORATION COMMISSION

Wanda Nichols
(Notary Public)

My commission Expires: 1-28-1980 DEC 22 1978