


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 36 Twp. 16 Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C S/2 S/2 NW
Lease Owner Bankoff Oil Company
Lease Name Kraft Well No. 3
Office Address Drawer 2479, Tulsa, Oklahoma 74101
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above Section Plot

Date Well completed 5-29 19 79
Application for plugging filed 5-29 19 79
Application for plugging approved 5-29 19 79
Plugging commenced 5-29 19 79
Plugging completed 5-29 19 79
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3400'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	334'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

50-50 Pozmix - 4% Gel. 60 sks. @ 390'
10 sks. @ 40'
2 sks. in rathole

By Allied. Job completed @ 8:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 8 1979


CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this Affidavit)
Name of Plugging Contractor Allen Drilling Company
P. O. Box 1389, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
Allen Drilling Company (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Smith
P. O. Box 1389, Great Bend, KS 67530
(Address)

Subscribed and sworn to before me this 31st day of May, 19 79



Wanda Nichols
Notary Public.

My commission expires 1-28-1980

DRILLER'S WELL LOG

DATE COMMENCED: 5-24-79
DATE COMPLETED: 5-29-79

Bankoff Oil Company
Kraft #3
C S/2 S/2 NW-Sec. 36-16-11W,
Barton County, Kansas

713- 721' Anhydrite
2953-2958' Shale
2958-3051' Lime and Shale
3051-3064' Lime and Shale
3064-3345' Lime
3345-3360' Lime and Shale
3360-3400' Shale, Lime, Chert and Sand
3400' RTD

ELEVATIONS 1918' K.B.
G.L.

FORMATION DATA

Anhydrite	713	+1205
Base Anhydrite	721	
Heebner	2953	-1031
Brown Lime	3051	-1133
Lansing	3064	-1146
Base Kansas City	3345	-1427
Conglomerate	3360	-1442
RTD	3400	-1482

SURFACE PIPE:

Ran 8 Jts. Used 28# 8 5/8" Casing.
Tally 330'. Set @ 334' w/185 sks.
60-40 Pozmix, 2% Gel, 3% c.c.
By Allied. P.D. 8:30 p.m.
Cement did circulate.

PLUGGING:

50-50 Pozmix - 4% Gel.
60 sks. @ 390'
10 sks. @ 40'
2 sks. in rathole
By Allied. Job completed @ 8:30 p.m.
Orders by Duane Rankin.

RECEIVED
STATE CORPORATION COMMISSION

JUN - 8 1979

CONSERVATION DIVISION
Wichita, Kansas

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

DALE L. SMITH, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Dale Smith

Subscribed and sworn to before me this 31st day of May 1979.

Wanda Nichols

(Notary Public)



My commission Expires: 1-28-1980