

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,576 - 0000

LEASE NAME ROSS "C"

WELL NUMBER #1

3300' Ft. from S Section Line

660' Ft. from E Section Line

SEC. 13 TWP. 28S RGE. 16 ~~XXXX~~ (W)

COUNTY Kiowa

Date Well Completed 12-4-79

Plugging Commenced 5-4-87

Plugging Completed 5-11-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202

PHONE# (316) 269-7600 OPERATORS LICENSE NO. 5171

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? YES

Which KCC Office did you notify? Unknown

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4672'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	10 jts	
				4-1/2"	115 jts	59 jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Dumped 100 gals sand down csg. Pulled & laid down 59 jts csg, capped off w/ cmt head. Pumped 3 sxs hulls, 15 gel, 50 sxs 60/40 poz w/ 6% gel, 10 gel, 1 sx hulls, 8-5/8" plug, 100 sxs 60/40 poz w/ 6% gel. Max pressure=500 psig. ISIP=300 psig.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hayes Well Service License No. 5429

Address Box 108, Attica, Kansas 67009

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey S. Childs

(Employee of Operator) or ~~operator~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jeffrey S. Childs

(Address) Jeffrey S. Childs
155 N. Mkt, Ste 1000, Wichita, KS. 67202

SUBSCRIBED AND SWORN TO before me this 12th day of May, 19 87

Connie F. Kessler
NOTARY PUBLIC

My Commission Expires: July 10, 1988

NOTARY PUBLIC

MAY 13 1987