

15-009-20372 0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Brougher Oil, Inc.

Complete Address P. O. Drawer 1367 Great Bend, Kansas 67540

Lease Name Alden "A" Well No. 1

Location C NE NE Sec. 36 Twp. 16 Rge. 11 (E) (W)X

County Barton Total Depth 3373'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:45 AM Day 27 Month 7 Year 1979

The above well was plugged as follows:

Sanded back to 3150' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

20 sx mud gel, 1 sx hulls, plug, and 100 sx cement.

Recovered approx. 1850' of 5 1/2" casing.

Top perforation at 3190' 1/4

Max pres 800#. Shut in pres. 500#.

3371' of 5 1/2" casing cemented with 150 sx cement.

265' of 8 5/8" surface casing cement circ.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 30 1979

7-30-79

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-31-79

INV. NO. 0101-W

Signed: [Signature]  
Well Plugging Supervisor