

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 62-23

LOCATION SE-11W-7E

SEC. 36 TWP. 16 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Beeford

Operator El Morado Refining Co Address Box 551 - El Morado - Kans.

Field _____ County Barton

Total Depth 3365 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 284 ft. Circulated with cement.
5/8" casing set at 3352 ft. Cemented with 100 sacks of
cement - Plugged back to 3190 ft with sand -
Dumped 5 sacks of cement at 3190 ft - ripped off & pulled
the 5/8" casing - mud to 284 ft - Set Rock Bridge &
15 sacks of cement at 284 ft - Mud to 30 ft - Plug
4 10 sacks of cement at the surface -
Shull Casing Pulling Co - Plugging Contractors*

REGISTERED
STATE CORPORATION COMMISSION

MAR 26 1951

PLUGGING
FILE SEC 56T-16R-11W
BOOK PAGE 62 LINE 73

CONSERVATION DIVISION
Wichita, Kansas C. W. Stough
District Conservation Agent

Date 3-22-51