

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW - NW - SW

SEC. 6 TWP. 21 RGE. 18-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Lewis

Operator Alhewich & Payne, Inc. Address 708-Phillips Bldg Tulsa Okla.

Field _____ County Pawnee

Total Depth 3786 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 980 ft - Circulated with cement.
5 1/2 casing set at 3786 ft. Plugged back to 3740
with chert & sand. Dumped 5 sacks of cement at 3740 ft.
Shot off & pulled the 5 1/2 casing - Filled hole with
heavy mud - Pumped in Plug & 100 sacks of
cement - Filling hole from 300 ft - to the
Surface with cement

RECEIVED
Conservation Div.

6-17-50

JUN 17 1950
PLUGGING
FILE SEC
BOOK PAGE

C. A. Storch
District Conservation Agent

Date 6-14-50