

B

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965
12-1-1965
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Jay Bergman Oil Company

Complete Address: 425 Union Center, Wichita, Kansas

Lease Name Keeler Well No. # 1

Location SE SW SW Sec. 17 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3490'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Jay Bergman Drilling Company

Address: 425 Union Center, Wichita, Kansas License No. 507

Operation Completed: Hour 11:00AM Day 28th Month Nov. Year 1965

The Above well was plugged as follows:

260' of 8 5/8" surface pipe, cemented with 175 sacks. 3490' of 4 1/2" long string,
cemented with 50 sacks. Top perferation 3436'. Bottom of the hole was sanded
to 3425', and cemented with 3 sacks. through the dump bailer. 1652' of 4 1/2" long
string was recovered from the hole. Fluid was up in the hole. Bridge plug was.
pushed in fluid to 250', rock bridge from 250' to 240'. 5 sacks of cement was
mixed in barrel, and put on plug at 240', through the dump bailer, and let set
over-night. Next morning hole was bailed dry, and 20 sacks of cement was added
to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12-1-65

INV. NO. 2310-w