

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20402-00-00
Spot: NWSESW Sec/Twnship/Rge: 8-31S-11W
1303 feet from S Section Line, 3501 feet from E Section Line
Lease Name: AXLINE B Well #: 2
County: BARBER Total Vertical Depth: 4397 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4395	2250	WITH 200 SX CMT
SURF	8.625	247		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/18/2017 1:30 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Revd. from: ALAN VRATIL Company: HERMAN L LOEB Phone: (620) 886-2419

Proposed Plugging Method: SANDBACK 4280' WITH 5 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2017 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4260' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 60 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4328	4346		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

INVOICED
AUG 28 2017

District: 01

Signed Stephan J. Pfeifer
(TECHNICIAN)

RECEIVED
JUL 25 2017
KCC DODGE CITY