

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-20594-00-00  
Spot: SESENEW Sec/Twnshp/Rge: 3-26S-8E  
1070 feet from N Section Line, 2520 feet from W Section Line  
Lease Name: CREW Well #: 26  
County: GREENWOOD Total Vertical Depth: 2650 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comment
<u>5697</u>	PROD	4.5	2586		125 SX
Op Name: <u>JACKSON BROTHERS, L.L.C.</u>	SURF	8.625	33		16 SX
Address: <u>116 E 3RD ST</u> <u>EUREKA, KS 67045</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2014 9:30 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Rcvd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50 ft. cement plug inside 4.500" casing at 2500-2450 ft. 2. 50 ft. cement plug inside and outside 4.500" at 1250-1200 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: NONE  
Date/Time Plugging Completed: 08/14/2014 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

spotted 7 sxs cement w/dump baler, ran tubing to 1250', pumped 30 sxs cement, pulled tubing to 250', pumped 60 sxs cement to surface, casing shot @ 11250' & 250', gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2541	2548		

RECEIVED  
KCC DIST # 3  
AUG 14 2017  
CHANUTE, KS

MH

INVOICED  
AUG 29 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Milo Heffern  
(TECHNICIAN)

810 E 7TH  
PO Box 92  
EUREKA, KS 67045  
(620) 583-5561



15-073-205940000

Cement or Acid Field Report  
Ticket No. **3441**  
Foreman Steve Mead  
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-14-17	1002	CRAW				Greenwood	Ks	
Customer			Safety Meeting		Unit #	Driver	Unit #	Driver
Jackson Bros. LLC					102	Rick		
Mailing Address					112	Jason		
116 E 38A					144	Kevin		
City								
Eureka								
State								
Ks								
Zip Code								
67045								

Job Type PTA Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/4 1250'  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety Meeting, Rig up to 2 3/4 tubing. Pump holes fresh water ahead.  
Spot 30 lbs cement at 1250'. Wait on rig to pull out tubing.  
Rig up to 4 1/2 casing. Break circulation w/ fresh water. Mix 60 lbs  
cement 250' to surface inside end of 4 1/2 casing. Well stop full.

Job Complete

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C202	905Ks	10/40 Permex Cement	12.75	1147.50
C206	300#	Gal 4 1/2	.20	60.00
C103A	3.87 Ton	Ton Mileage Bulk Truck	89/c	345.00
C113	4 hrs	Bobcat Truck	85.00	340.00
<div style="border: 1px solid black; border-radius: 50%; padding: 10px; display: inline-block;">           6% (195.00)            \$2159.16         </div>				
			Subtotal	2701.75
			Sales Tax	207.63
			<b>250%</b>	
Authorization _____ Title _____			Total	<b>2909.38</b>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.