

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-20783-00-00  
Spot: W2W2NENW Sec/Twnshp/Rge: 13-14S-15W  
660 feet from N Section Line, 1555 feet from W Section Line  
Lease Name: NIEDENTHAL Well #: 2  
County: RUSSELL Total Vertical Depth: 3262 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 4.5   | 3260       |             | 125 SX   |
| SURF   | 8.625 | 283        |             | 175 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2017 10:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (214) 219-8883

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.  
Well has been squeezed. No perforating required.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2017 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3200' and pumped 100 sx cement. Pulled tubing to 1600' and pumped 70 sx cement. Pulled tubing to 600'. Circulated cement to surface with 35 sx cement. Pulled tubing and topped off with 10 sx cement pressured at 400 psi. Surface pipe has cement at well bradenhead.

GPS: 38.84005 -098.94193

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUN 13 2017

Form CP-2/3

INVOICED  
AUG 29 2017