

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-001-25944-00-00
Spot: NWSWSWNE Sec/Twnshp/Rge: 8-26S-19E
3135 feet from S Section Line, 2475 feet from E Section Line
Lease Name: JARRED Well #: 4
County: ALLEN Total Vertical Depth: 828 feet

Operator License No.: 31729
Op Name: OWENS, KEITH DBA OWENS OIL
Address: 1560 2400TH ST
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	828		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2017 12:00 AM
Plug Co. License No.: 30948 Plug Co. Name: CONLEY, HARRY
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed
Plugging
Method:

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 02/27/2017 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.875" casing to TD. Pumped cement through the 1" pipe inside the 2.875" and placed 5 sack plug at TD. Pulled pipe to 250'. Pumped and circulated cement from 250' to surface. Pulled pipe and topped well off with cement. A total of 13 sacks of portland cement was used to plug this well.

RECEIVED
KCC DIST # 3
JUL 07 2017
CHANUTE, KS

RD

Remarks: PLUGGING WAS NOT CALLED INTO DISTRICT #3 OFFICE.

Plugged through: TBG

District: 03

Signed, *Ryan Duling*
(TECHNICIAN)