

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01356-00-01
Spot: SWSWNENW Sec/Twnshp/Rge: 18-32S-14W
4171 feet from S Section Line, 3791 feet from E Section Line
Lease Name: STUMPH SMITH A Well #: 2
County: BARBER Total Vertical Depth: 4822 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		WITH 2 SX CMT
PROD	5.5	4822	0	WITH 100 SX CMT
SURF	8.625	227		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/29/2017 10:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Revd. from: CHUCK TONER Company: PPSI Phone: (620) 546-4752

Proposed Plugging Method: SET CIBP @ 4700' WITH 2 SX CMT. PERFORATE AT 870' & PUMP 50 SX CMT. PERFORATE AT 270' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE & PRESSURE TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 06/29/2017 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4700' WITH 2 SX CMT. PERFORATE AT 870' & PUMPED 50 SX CMT WITH 100# HULLS. NEVER PRESSURED UP. RAN TBG BUT NEVER TAGGED ANYTHING. PUMPED ANOTHER 50 SX CMT. PRESSURED TO 300#. SHUT IN FOR OVER 1 HOUR. TAGGED CMT AT 340'. PERFORATE AT 270'. CIRCULATED CMT TO SURFACE WITH 75 SX CMT. PULLED TBG & TOPPED OFF WITH 10 SX CMT. CHECK BACKSIDE TO 300#. TOOK NO CMT.

Perfs:


Top	Bot	Thru	Comments
4749	4802		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL - 7 2017

KCC DODGE CITY

Form CP-2/3

INVOICED
AUG 29 2017