

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01194-00-00

Spot: NENESE

Sec/Township/Rge: 3-32S-15W

2134 feet from S Section Line,

346 feet from E Section Line

Lease Name: SKINNER D

Well #: 3

County: BARBER

Total Vertical Depth: 4926 feet

Operator License No.: 31142

Op Name: PETROLEUM PROPERTY SERVICES, IN

Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

CIBP		4810		WITH 2 SX CMT
------	--	------	--	---------------

L1	4.5	4850		WITH 125 SX CMT
----	-----	------	--	-----------------

PROD	5.5	4925	0	WITH 100 SX CMT
------	-----	------	---	-----------------

SURF	8.625	222		WITH 190 SX CMT
------	-------	-----	--	-----------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/23/2017 1:00 PM

Plug Co. License No.: 34275

Plug Co. Name: SCOTT SERVICES LLC

Proposal Revd. from: KELLY SCHMEIDLER

Company: PETROLEUM PROPERTY SERVICES Phone: (620) 546-4752

Proposed Plugging Method: SET CIBP @ 4800' & 2 SX CMT. PERFORATE 4 1/2" LINER AT 960'. RUN TBG IN TO 960' & PUMP 35 SX CMT WITH 100# HULLS & 40 SX CMT. PERFORATE 4 1/2" LINER AT 260'. PUMPED DOWN CASING WITH CMT FILLING 4 1/2" LINER & 8 5/8" X 5 1/2" ANNULUS TO SURFACE WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/26/2017 10:00 AM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4810' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 4 1/2" LINER AT 960'. RUN TBG INTO 960' PUMPED DOWN TBG WITH 35 SX CMT, 100# HULLS, 40 SX CMT. PERFORATE 4 1/2" LINER AT 260'. SHUT DOWN. 6/26/17: PUMPED DOWN 4 1/2" LINER WITH 72 SX CMT FILLING 4 1/2" LINER & 8 5/8" X 5 1/2" ANNULUS FROM 260' TO SURFACE.


Top	Bot	Thru	Comments
4860	4880		

Remarks: USED COMMON CEMENT BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

JUL - 7 2017

KCC DODGE CITY

INVOICED
AUG 29 2017